

Originator Engineering	Item Order Project: 2014-901 Storm Sewer Maintenance Project
Agenda Section Consent Business	Date 4/21/2014

Description

The City Council is requested to consider ordering the 2014-901 Storm Sewer Maintenance Project. This project includes maintenance and construction of the storm sewer system at approximately seventeen sites.

Project sites include the following:

- Normandale Boulevard, near W. 100th St. – Plug and fill corroded metal storm sewer pipe.
- 4600 Overlook Drive – Reconstruct Overlook Lake outlet pipe and structure.
- Minnesota Drive, between Johnson and France Ave. – Rehabilitate corroded metal storm sewer pipe.
- West 90th St. near Tretbaugh Dr. – Replace storm sewer pipe, construct one water quality structure and remove accumulated sediment.
- Nine Mile Creek at 2501 Ivy Lane – Replace storm sewer pipe and stabilize streambank.
- 218/294 Mission Circle – Replace Four catchbasins.
- 10201 11th Avenue, Mound Springs Park – Replace 750 linear feet of 36” diameter storm sewer outfall pipe and one manhole, and trail, slope and tree restoration.
- 8501 17th Avenue, Wright’s Lake – Replace outlet structure overflow grate.
- 1700 W. 98th Street, Public Works Facility – Replace deteriorated pervious concrete surfacing with pervious pavers and bituminous surfacing.
- Lyndale Avenue at approximately 108th St. – Construct subgrade draitile system.
- Reline storm sewer pipe at seven sites.

Residents living in the vicinity of these sites will be notified of the pending construction and, if necessary, informational meetings will be held. Construction is anticipated to begin in July 2014.

Funding (up to \$470,000) is included in the Storm Water Drainage Utility Budget, under Fund 530-8320-433-70-31, and no assessments will be involved in the project.

Requested Action

Staff recommends that Council order the 2014-901 Storm Sewer Maintenance Project.

Attachments: